

QUICK FACTS

- Goal:** Install a dock leveller and shelter
- Solution:** Remanufacture mounts for the dock bumpers, manufacture a support frame.
- Result:** Dock leveller installed with shelter centralised meeting customer's expectations.

THE ISSUE

A customer had moved into an existing property and required a dock leveller and shelter to be installed. The wall the A B Equipment team would mount the shelter to was manufactured from Colorbond™ sheeting and not suitable for this application. The opening in the wall, when originally fabricated, was offset and now caused an issue and the team could not centralise the new shelter.

BEFORE PHOTOS



Together **E**veryone **A**chieves **M**ore

THE RESOLUTION

To commence this project, A B Equipment's Melbourne-based team had to remanufacture mounts for the dock bumpers. Then install the dock leveller (colour coded) to the customer's specifications.

With this work completed, A B Equipment was able to manufacture a support frame attaching it to the door opening frame, and that was attached to the dock shelter. This enabled the team to centralise the shelter with the door opening.

These works were completed within two days to the complete satisfaction of the builders and client, enabling they could commence transfer of stock earlier than anticipated.

AFTER PHOTOS



Together **E**veryone **A**chieves **M**ore